BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

DRAFT TENDER SCHEDULE –'B'

Item No:
Original / Duplicate

Name of Work:- Drilling of Borewells in Yelahanka old town areas in ward No:02 of Yelahanka sub division

Sl	Description	Unit	Approved Qty	Approved Rate	Rates in words
1	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.48, I. 9.4) PRED SR 2012-13	Each BW	4.00	1938.46	Rueeps one thousand nine hundred thity eight and paise forty six only
2	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13	Rmtr			
	0 to 50 m		200.00	315.18	Rupees three hundred fifteen and paise eighteen only
	50 to 100 m		200.00	412.00	Rupees four hundred twelve only
	100 to 150 m		200.00	458.35	Rupees four hundred fifty eight and paise thity five only
	150 to 200 m		200.00	484.10	Rupees four hundred eighty four and paise ten only

Sl	Description	Unit	Approved Qty	Approved Rate	Rates in words
	200 to 250 m		200.00	560.32	Rupees five hundred sixty and paise thirty two only
	250 to 300 m		200.00	600.49	Rupees six hundred and paise forty nine only
	300 to 350 m		80.00	640.66	Rupees six hundred forty and paise sixty six only
3	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985. one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and duties) Prices include Collar medium duty P. iii, I No. 84 PRED SR 2012-13	Rmtr	180.00	1325.00	Rupees one thousand three hundred twenty five only
4	Providing 200mm dia PVC Pipe 10kg/cm2 PRED Bangalore circle SR2012-13 P.N 15, I No 3.43	Rmtr	60.00	1721.13	Rupees one thousand seven hundred twenty one and paise thirteen only
5	Providing and fixing 160mm Borewell Cap P. iii, I No. 85 PRED SR 2012-13	Each	4.00	100.00	Rupees one hundred only
6	Providing and fixing 175mm dia MS Collar PRED Bangalore circle SR2012-13 P.N iii, I No 86	Each	32.00	150.00	Rupees one hundred fifty only
7	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps PWD SR 2015-16 P. XXXX Item No. 24 including of all taxes 12.5 HP 25 Stage	No	4.00	70600.00	Rupees seventy thousand six hundred only

Sl	Description	Unit	Approved Qty	Approved Rate	Rates in words
8	KSRB13-3.6 : Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 Page No. 89, Item No. 13.15 PWD SR 2016-17	m	1200.00	457.92	Rupees four hundred fifty seven and paise ninety two only
9	Heavy Duty Collar 50 mm dia	No	200.00	130.00	Rupees one hundred thirty only
10	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A P No. 12 / I No. 2.10.4(1) 3C x 4 Sqm mm KPWD Electrical SR 2014-15	Mtr	2400.00	188.70	Rupees one hundred eighty eight and paise seventy only
11	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) Page No. 558, Items No-3 BWSSB SR for 2014-15)	er Lengt	180.00	88.00	Rupees eighty eight only
12	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 44 / I No. 6.6.6 KPWD Electrical SR 2014-15	Each	4.00	302.00	Rupees three hundred two only
13	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15	Mtr	200.00	140.40	Rupees one hundred forty and paise forty only
14	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15	Mtr	200.00	10.80	Rupees ten and paise eighty only
15	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) P No. 61 / I. No. 7.9.3 KPWD Electrical SR 2014-15 For Cutting Road Surface	Mtr	100.00	85.00	Rupees eighty five only
16	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15	Mtr	8.00	345.00	Rupees three hundred forty five only

Sl	Description	Unit	Approved Qty	Approved Rate	Rates in words
17	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15 16Sqmm	No.	4.00	280.00	Rupees two hundred eighty only
18	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, (P No. 55, I No. 7.1) KPWD Electrical SR 2014-15	No	4.00	2727.00	Rupees two thousand seven hundred twenty seven only
19	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.P No. 44 / I No. 6.7.2 KPWD Electrical SR 2014-15 32 Amps	No.	12.00	180.00	Rupees one hundred eighty only
20	KSRB13-7.1-4 : Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No KBS 13.2.10 / 13.13 Page No. 93, Item No. 13.55, PWD SR 2016-17	Nos	4.00	1585.76	Rupees one thousand five hundred eighty five and paise seventy six only
21	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete - for 50mm dia: Page No. 95 , Item No. 13.81.3 PWD SR 2016-17 50mm dia	Each	4.00	227.90	Rupees two hundred twenty seven and paise ninety only
22	Supplying and fixing 50 mm dia GI X nipple with ISI mark with all lead and lift loading uloading and labour charges etc., Complete as per spicification	No	16.00	80.00	Rupees eighty only
23	Supplying shunt capaitors conforming to IS 2834 3 phase 400/440 volts grade for power factor improvements of rotaing machinery capacitor in KVAR rating Nos 2KVAR capacity with all lead and lift loading uloading and labour charges etc., Complete as per spicification	No	4.00	350.00	Rupees three hundred fifty only
24	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps Group A TPN P No. 47 / I No.6.16.5 KPWD SR 2014-15	No	4.00	1547.00	Rupees one thousand five hundred forty seven only
25	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete P.No. 57, I. No. 6.41.2 KPWD Electrical SR 2014-15 16SWG	Sq.Cm	86400.00	0.33	Paise thirty three only

Sl	Description	Unit	Approved Qty	Approved Rate	Rates in words
26	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset 12.5HP to 15 HP Star Delta Starter SERDED Rate	No.	4.00	11000.00	Rupees eleven thousand only
27	Cutting of roads surface for pipeline trenches and disposing the excavated stuff as directed including barricadding danger lightingetc., in the asphalt surface road (PN 257.I.N 37.38)	Cum	21.00	340.00	Rupees three hundred forty only
28	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3)	Cum	78.75	189.00	Rupees one hundred eighty nine only
29	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure 75mm outside diameter with special flange, compression type fittings, wall clips , making good the wall, ceiling and floor including cost all material, labour charges, HOM of equipments and testing complete as per specifications (P.N .93 I N 13.70.3)	Rmtr	100.00	320.12	Rupees three hundred twenty and poaise twelve only
30	63mm dia 6 KSC PVC pipe	Rmtr	75.00	289.38	Rupees two hundred eighty nine and paise thirty eight only
31	Refilling available earth around pipelines, cables in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering lead upto 50m and lift upto 1.5m including cost of labour complete as per specification (P.No.6 I.No.2.11)	Cum	78.75	61.00	Rupees Sixtyone only
32	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 92 / I.13.37 PWD SR 2016-17	Each	4.00	2175.12	Rupees two thousand one hundred seventy five and paise twelve only

"DTS Approved"

16.4.18

Executive Engineer,
Yelahanka Division,
BBMP, Bangalore.